

Notice of Addendum #2 - February 13, 2026

PROJECT: St. Tammany Fire Protection District No. 1
Fire Station #10
2745 Lakeshore Vista Blvd.
Slidell, LA 70461

PROJECT NO.: 2519

FROM: DAMMON ENGINEERING
554 Old Spanish Trail
Slidell, LA 70458
(985) 649-5832

TO: All on Record Holding Bidding Documents

This Addendum forms a part of the Contract Documents and modifies the original Bidding Documents dated December 3, 2025. The contents of this Addendum shall be included in the Contract Documents when the Agreement is executed. Changes made by this Addendum take precedence over the Documents of earlier date.

Acknowledge receipt of this Addendum in the space provided on the Bid Form.

GENERAL

1. The addendum is to be distributed to registered Plan Holders via Central Bidding.

MODIFICATIONS TO THE SPECIFICATIONS

2. 133419 , Metal Building Systems, Part 2 - Products, paragraph 2.1 Manufacturers, add the following sub paragraphs:

C-21 Pinnacle Structures, Inc.
C-22 Ideal Steel Buildings and Components

MODIFICATIONS TO THE DRAWINGS

3. **Sheet P103:** Added gear washer plumbing sizes and apparatus bay catch basin size.
4. **Sheet E103:** Added Airvac 911 system control diagram. Changed note to read 400 amp Automatic Transfer Switch. Contractor shall provide ATS to match generator.
5. **Sheet A503:** Changed door tag 117C to read 14'x14'

GENERAL QUESTIONS

The following questions were submitted. Answers are in bold.

6. Please advise on what type of piping we are to use for the building soil, waste and vent applications.

Schedule 40 PVC piping is acceptable below grade and Schedule 80 PVC piping is acceptable above grade.

7. Please clarify what is the wind speed design requirements are.

The wind speed design shall be 140 mph wind load, risk category II and the wind exposure is C.

8. What are the specifications for the generator and transfer switch.

The generator is a Generac 100KW and will be provided by owner with a stand. The transfer switch that is designed is a Honeywell HX611 series transfer switch rated at 400 amps to be provided by the contractor. See attached specification sheets. Once generator is installed, Generac will conduct a 4 hr start up and a 4 hr test load paid for by owner.

9. How many garage doors are there.

Four 14'x14' with motors and One 8'x7' manual. All garage doors are insulated, Powder coated and the color shall be Red Light Red. Motors are lift master 3/4 hp Jackshaft with remotes and sensors, sensors shall be installed such that garage doors operate both inside and outside for a distance of 100 ft.

SUBSTITUTIONS

10. Lighting supply companies that submitted as an approved substitution: Curtis Stout lighting only. WKA lighting only. Sesco lighting only. Bell & McCoy lighting only.

11. Alarm companies: Honeywell

ADDENDUM No. 01 CONSISTS OF:

Addendum Cover Letter and Narrative (2 pages)
DRAWING SHEETS (3 pages)
SKETCHES (1 page)
SKC1 Fence Detail
Generator Specs (6 pages)
for a total of (12 pages) TWELVE DOCUMENT SHEETS

*All planholders must acknowledge receipt of this addendum via the
LOUISIANA UNIFORM PUBLIC WORK BID FORM.*