

PRELIMINARY PLAN PAYMENT MILESTONES

Payment Milestones	Task Status	Road Tasks	Bridge Tasks	Common Tasks
30 % Distribution	Completed	<ol style="list-style-type: none"> 1. Plan/profile sheets with existing topo 2. Preliminary typical sections submitted for review 3. Title sheet 4. Typical section questionnaire distributed 	<ol style="list-style-type: none"> 1. Bridge hydraulic study and scour analysis 2. Type, Size & Location of Structure Set 3. Deep borings 	<ol style="list-style-type: none"> 1. Predesign criteria established 2. Horizontal & vertical alignment set
	In Progress	<ol style="list-style-type: none"> 1. Preliminary typical sections being reviewed 2. Pavement Design 3. Soil borings and pH/resistivity data 4. Capacity analysis 	<ol style="list-style-type: none"> 1. Superelevation diagram 2. Economic study (if appropriate) 	
60% Distribution	Completed	<ol style="list-style-type: none"> 1. Horizontal/vertical alignment on plan/profile sheets 2. Geometric details submitted for review 3. Hydraulic design submitted for review 4. Cross sections and required right of way 5. Final typical section 	<ol style="list-style-type: none"> 1. Preliminary design of substructure & 2. Foundation analysis 3. General Plan 4. Typical bridge sections 	
	In Progress	<ol style="list-style-type: none"> 1. Earthwork computations 2. Construction notes & details 	<ol style="list-style-type: none"> 1. Span and bent details 2. Foundation layout 3. Framing plan 	<ol style="list-style-type: none"> 1. Sequence of construction & construction signing
90 % Distribution	Completed	<ol style="list-style-type: none"> 1. Geometric and hydraulic comments incorporated 2. Pre-plan in hand review 	<ol style="list-style-type: none"> 1. Bridge quantities and general notes 	<ol style="list-style-type: none"> 1. Assemble plans 2. Cost estimate
	In Progress			<ol style="list-style-type: none"> 1. Pre-plan in hand review
95 % Distribution	Completed			<ol style="list-style-type: none"> 1. Plan in hand prints distributed
100 % Distribution	Completed			<ol style="list-style-type: none"> 1. Plan in hand inspection and comments addressed 2. Right of way taking lines set and transmitted to Location and Survey 3. Permit sketches 4. Revised cost estimate

Figure 1-7 (Continued on next page)

FINAL PLAN PAYMENT MILESTONES

Payment Milestones	Task Status	Road Tasks	Bridge Tasks	Common Tasks
30 % Distribution	Completed	1. Submit final typical sections for review & approval	1. General plan 2. Framing plan 3. Superstructure design	
	In Progress	1. Review R/W maps 2. Finalizing hydraulic design 3. Finalizing vertical & horizontal geometry 4. Finalizing construction notes	1. Foundation layout 2. Lighting and signing design 3. Superstructure details 4. Substructure design	
60% Distribution	Completed	1. Submit for final drainage design review	1. Superstructure details 2. Substructure design 3. Foundation layout 4. Lighting and signing design	1. Submit for sequence of construction and
	In Progress	1. Summary sheets 2. Joint Layouts 3. Graphical grades	1. Substructure details 2. General notes 3. Summary of quantities	
90 % Distribution	Completed			1. Pre-ACP submitted for review prior to distribution
95 % Distribution	Completed			1. Advance Check Print distribution 2. Cost estimate
	In Progress			1. Special Provisions
98 % Distribution	Completed			1. ACP comments addressed 2. Final cost estimate 3. Entire set of original plan sheets transmitted to 4. Special provisions
100 %	Completed			1. Plans, Specifications & Estimate 2. Plans & Estimate transmitted to General Files

Figure 1-7 (Continued from previous page)