



Phase I: Lay pipe required for detour. Construct detour.

Phase II: Shift traffic to detour. Remove existing roadway/bridge.
Lay pipe required for roadway, using temporary slopes to minimize length. Construct roadway.

Phase III: Return traffic to mainline. Remove detour roadway & pipe.
Extension not required for mainline. Remove and relocate a portion of the extension, to adequately finish outside mainline slope. Complete grading and earthwork required to establish design sideslopes.

Figure 4-19: Three Phase Pipe Detour