

PACKAGED A/C SCHEDULE – Covington

ROOFTOP UNIT															
TAG	AREA SERVED	Make/Model	Model / Size	Nominal Tonnage	Total CFM	OA CFM	External SP ("WC)	HEAT		FILTERS	POWER			MCA	REMARKS
								KW	STAGE		VAC	PH	Hz		
RTU-C3	Gym Stage	Trane	TSH150-3RK	12.5	4000	2680	0.6	27	2	MERV-8 MERV-8	208	3	60	109	1, 2, 3, 4
RTU-C4	Gym Stage	Trane	TSH150-3RK	12.5	4000	2680	0.6	27	2	MERV-8 MERV-8	208	3	60	109	1, 2, 3, 4

NOTES:

- 1 Cooling capacities to be rated in accordance with AHRI standard 210/290 for ASHRAE standard design weather conditions in New Orleans, LA.
- 3 Provide single point connection. Install units in accordance with manufacturer's recommendations.
- 2 Provide controls per attached drawings and specifications
- 4 Provide new filters after commissioning and final acceptance.