



GENERAL NOTES

1. FOR DETAIL ROOM INFORMATION AND CABINET DETAILS REFER TO A-0 SHEETS.
2. COORDINATE WITH OWNER WHEN DEMOLITION WILL BEGIN IN ORDER FOR THE OWNER TO REMOVE NECESSARY EQUIPMENT.
3. REMOVE THREE DAY NOTICE PERMITS TO BEGIN THROUGHOUT THE CONSTRUCTION PROGRAMS.
4. CONTRACTOR TO MAINTAIN MEANS OF EGRESS THROUGHOUT THE CONSTRUCTION PROGRAMS.
5. Gypsum Board to continue to underside of roof deck around all treatment rooms.

SPECIFIC NOTES

- 1 REMOVE EXISTING WALL AND PATCH.
- 2 SAW CUT EXISTING WALL FOR NEW DOOR INSTALLATION.
- 3 REMOVE EXISTING HOLLOW METAL DOOR AND INSTALL 2"x6" METAL STUD @ 16" O.C. AND INSTALL GYPSUM BOARD.
- 4 TAPE, FLOAT, AND PAINT GYPSUM BOARD WALL.
- 5 REMOVE EXISTING PLUMBING FIXTURES AND CAP SEWER LINES. (SEE MECHANICAL DRAWINGS.)
- 6 ADD STAINLESS STEEL CORNER GUARD.
- 7 REMOVE AND REPLACE EXISTING CEILING.
- 8 INSTALL COLUMN COVER AS DETAIL. (SEE DETAIL J-13/A.7.7)

AREA CALCULATIONS

EXISTING RENOVATED AREA	742.75 SQ. FT.
NEW HEATED AREA	11,491.83 SQ. FT.
CANOPY AREA	4,112.01 SQ. FT.
TOTAL AREA	16,346.60 SQ. FT.

LEGEND

- 1 HOUR FIRE RATED WALLS - U465
- 2 HOUR FIRE RATED WALLS
- FIRE PARTITION - U438
- FIRE EXTINGUISHER



St. Charles Parish Hospital Construction Project
Emergency Department Construction Project

FLOOR PLAN

File name	A.1.1.dwg
Drawing number	
Project number	0910
Date	04/21/2010
Phase	Construction documents

A.1.1