FILE NAME: J:_Hospital - Medical - Dental\2313 - Diana Oaks Facility Master\Current Drawings to Use\A2.0 - Finish Schedule.dwg PLOT DATE & TIME: Tuesday, June 3, 2025 3:22:25 AM

FINISH SCHEDULE

ROOM NUMBER	ROOM NAME	FLOOR FINISH	BASE MATL	WALL FINISH	CEILING	MILLWORK	COUNTERTOPS	Ceiling Height	COMMENTS
100	WAITING	LVT-1	WB-1	P-1, CTW-1, GTW-1	GYP-1	N/A	N/A	12' - 0"	NORTH WALL IN WAITING TO RECIEVE CTW-1, NORTH WALL WHERE DRINKING FOUNTAINS ARE LOCATED TO RECEIVE GTW-1
100A	RECEPTION	LVT-1	WB-1	P-4, STW-1	GYP-1	MW-1,PL-2	QTZ-1,PL-1	10' - 6"	STW-1 TO BE LOCATED ON WEST WALL FULL HEIGHT
101	WAITING RESTROOM	PTF-1	N/A	CTW-2 UP TO 72"H AFF, P-4	GYP-1	MW-1	SS-1	10' - 0"	CTW-2 LOCATED ON ALL WALLS, FULL-HEIGHT BEHIND MIRROR. P-4 TO BE LOCATED ABOVE CTW-2
102	DR. PARRY'S OFFICE	LVT-1	MRB-1	P-1	ACT-1	PL-2	N/A	10' - 0"	
103	CONSULT	LVT-1	MRB-1	P-1	ACT-1	N/A	N/A	10' - 0"	
104	NURSING OFFICE	LVT-1	RB-1	P-1	ACT-1	N/A	N/A	10' - 0"	
105	CONSULT	LVT-1	MRB-1	P-1	ACT-1	N/A	N/A	10' - 0"	
106	CLEAN UTILITY	WRBF-1	FCB-1	P-1	ACT-1	SSM-1	PL-1	10' - 0"	
107	COLLECTION	LVT-1	RB-1	P-1	ACT-1	PL-2	SS-1	10' - 0"	
108	CONFERENCE/ BREAK	L VT-1	RB-1	P-1, CTW-4 BACKSPLASH	ACT-1	PL-2	SS-1	10' - 0"	
109	COLLECTION	LVT-1	RB-1	P-1	ACT-1	PL-2	SS-1	10' - 0"	
110	PHLEBOTOMY	LVT-1	RB-1	P-1	ACT-1	PL-2	PL-1	10' - 0"	
111	PRIMARY LAB	WRBF-1	FCB-1	P-5	GYP-3	N.I.C.	EPC-1	8' - 0"	
112	OFFICE	LVT-1	RB-1	P-1	ACT-1	N/A	N/A	10' - 0"	
113	OFFICE	LVT-1	RB-1	P-1	ACT-1	N/A	N/A	10' - 0"	
114	OFFICE	LVT-1	RB-1	P-1	ACT-1	N/A	N/A	10' - 0"	
115	LIQUID N2 STORAGE	SSF-1	SSB-1	SSW 72" AFF, P-1	ACT-1	N/A	N/A	10' - 0"	
116	ELECTRIC	SC-1	N/A	P-1	ACT-1	N/A	N/A	10' - 0"	
117	TANK EXCHANGE	SC-1	N/A	P-1	ACT-1	N/A	N/A	10' - 0"	
118	DIRTY UTILITY	WRBF-1	FCB-1	FRP-1 UP TO 48"H, P-1	ACT-1	PL-2	SSC-1	10' - 0"	P-1 LOCATED ABOVE FRP-1
119	CLEAN LINEN	SC-1	N/A	P-1	GYP-1	N/A	N/A	10' - 0"	
120	DIRTY LINEN	SC-1	N/A	FRP-1 UP TO 48"H, P-1	GYP-1	N/A	N/A	10' - 0"	
121	TRASH	SC-1	N/A	FRP-1 UP TO 48"H, P-1	GYP-1	N/A	N/A	10' - 0"	
122	RISER ROOM	SC-1	N/A	P-1	GYP-1	N/A	N/A	10' - 0"	
123	CONSULT	LVT-1	MRB-1	P-1	ACT-1	N/A	N/A	10' - 0"	
124	OFFICE	LVT-1	MRB-1	P-1	ACT-1	N/A	N/A	10' - 0"	
125	FINANCIAL COUNSELING	LVT-1	MRB-1	P-1,4	ACT-1	N/A	N/A	10' - 0"	P-4 TO BE LOCATED ON SOUTH WALL
126	STAFF RESTROOM	PTF-1,2	N/A	CTW-3 UP TO 72"H AFF,P-4, PTW-4	GYP-1 EPOXY	MW-1	SS-1	10' - 0"	SHOWER TO RECEIVE PTF-2, SHOWER WALLS TO BE CTW-4, CTW-2 LOCATED ON ALL WALLS, P-4 TO BE LOCATED ABOVE CTW-2
127	VITALS	LVT-1	MRB-1	P-1	ACT-1	PL-2	PL-1	10' - 0"	
128	CORRIDOR	LVT-1	MRB-1	P-1	ACT-1	PL-2	PL-1	10' - 0"	
129	EXAM 1	LVT-1	RB-1	P-1,4	GYP-1	PL-2	PL-1	9' - 0"	P-4 TO BE LOCATED ON TV WALL
130	PATIENT RESTROOM	PTF-1	N/A	CTW-3 UP TO 72"H AFF,P-4	GYP-1	MW-1	PL-1	9' - 0"	CTW-2 LOCATED ON ALL WALLS, P-4 TO BE LOCATED ABOVE CTW-2
131	EXAM 2	LVT-1	RB-1	P-1,4	GYP-1	PL-2	PL-1	9' - 0"	P-4 TO BE LOCATED ON TV WALL
132	STORAGE	VCT-1	RB-1	P-1	GYP-1	N/A	N/A	9' - 0"	
133	NURSING STATION	LVT-1	MRB-1	P-1	ACT-1	PL-2	PL-1	10' - 0"	
134	GAS TANKS	VCT-1	RB-1	P-1	ACT-1	N/A	N/A	10' - 0"	
135	ADVANCED LAB	WRBF-1	FCB-1	P-5	GYP-3	N/A	N/A	8' - 0"	
136	ADVANCED PROCEDURE ROOM	WRBF-1	FCB-1	P-5	GYP-3	N.I.C.	EPC-1	8' - 0"	
137	CORRIDOR	LVT-1	MRB-1	P-1	ACT-1	PL-2	PL-1	10' - 0"	
138	EXAM 3	LVT-1	RB-1	P-1,4	GYP-1	PL-2	PL-1	9' - 0"	P-4 TO BE LOCATED ON TV WALL
139	EXAM 4	LVT-1	RB-1	P-1,4	GYP-1	PL-2	PL-1	9' - 0"	P-4 TO BE LOCATED ON TV WALL
140	PATIENT RESTROOM	PTF-1	N/A	CTW-3 UP TO 72"H AFF,P-4	GYP-1	MW-1	SS-1	9' - 0"	CTW-2 LOCATED ON ALL WALLS, P-4 TO BE LOCATED ABOVE CTW-2
141	EXAM 5	LVT-1	RB-1	P-1,4	GYP-1	PL-2	PL-1	9' - 0"	P-4 TO BE LOCATED ON TV WALL
200	DATA	PLY-1	N/A	P-1	ACT-1	N/A	N/A	8' - 0"	
201	MECHANICAL MEZZANINE	PLY-1	N/A	P-1	EXP	N/A	N/A	0"	

Grand total: 45

FINISH LEGEND

NOTE: CONTRACTOR AND SUBCONTRACTOR TO REFERENCE MANUFACTURER'S SPECIFICATIONS FOR RECOMMENDED INSTALLATION METHODS.

FLOOR

ACRONYM	TYPE	DESCRIPTION
LVT-1	Luxury Vinyl Floor	Interface Product: Natural Woodgrains #A002 Color: Black Walnut Size: 9.845" x 39.38" x 4.5"mm thick Backing: Commercial Grade Installation Method: Ashlar Note: Floating Floor w/ TacTiles Glue-Free Installation System
PLY-1	Unfinished Plywood	
PTF-1	Porcelain Tile Floor	Atlas Concorde Product: Sign Color: Greige Size: 12" x 24" Thickness: 9mm Finish: Matt Installation Method: 1/3 running bond running east to west Grout: Laticrete Marble Beige #17 Note: Hold all grout joints to minimum requirement by TCNA
PTF-2	Porcelain Tile Floor	Daltile Product: Keystones Color: Uptown Taupe Speckle #D202 Size: 2" x 2" mosaic on 12"x24" sheet Thickness: 1/4" Finish: Unglazed Installation Method: straight laid running east to west Grout: Laticrete Dusty Grey #60 Note: Hold all grout joints to minimum requirement by TCNA
SC-1	Sealed Concrete	
SSF-1	Stainless Steel Floor	
WRBF-1	Welded Rubber Floor	Nora Product: Noraplan Sentica Color: Frost Bite #6524 Size: 48" x 39' rolled goods Thickness: 3mm Note: Coordinating cold weld rod needed To be installed with coordinating flash cove (FCB-1)
VCT-1	Vinyl Composition Tile	Armstrong Product: Striations BBT Color: Steel Size: 12" x 24" Thickness: 1/8" Installation Method: Running Bond Run parallel to length of room

BASE

ACRONYM	TYPE	DESCRIPTION
FCB-1	Flash Cove Base	Nora Product: Noraplan Sentica Color: Frost Bite #6524 Size: 4"H x 39' rolled goods
MRB-1	Millwork Rubber Base	Johnsonite Product: Inflection #MW-48-G Color: Grey WG Size: 5 1/4"H x 8' continuous roll Thickness: 3/8"
RB-1	Rubber Base	Johnsonite Product: Traditional Wall Base #48 Color: Grey WG 4"H x 120' continuous roll
SSE	Stainless Steel Base	Stainless steel flash cove base
WB-1	Wood Base	5 1/4"H poplar wood base/painted Profile: to match Johnsonite Inflection #MW-01-G Color: Painted P-2

WALL

ACRONYM	TYPE	DESCRIPTION
CTW-1	Ceramic Tile Wall	Atlas Concorde Product: 3/D Wave Color: White Finish: Glossy Size: 15 3/4" x 31 1/2" Thickness: 10mm Grout: Laticrete Bright White #44 Installation Method: Vetical Stack Bond, tile to run vertical Hold all grout joints to minimum requirement by TCNA
CTW-2	Ceramic Tile Wall	Daltile Product: Showscape #SH09 Color: Stylish White Finish: Arabesque Size: 12" x 24" Thickness: 3/8" Grout: Laticrete Bright White #44 Installation Method: Vetical Stack Bond, tile to run vertical Trim: 12" Jolly Trim #S-1/212J Note: Tile to be installed 72"H Schluter QUADEC-K in finish AE to be used at all outside corners Hold all grout joints to minimum requirement by TCNA
CTW-3	Ceramic Tile Wall	Daltile Product: Showscape #SH09 Color: Stylish White Finish: Reverse Dot Size: 12" x 24" Thickness: 3/8" Grout: Laticrete Light Pewter #90 Installation Method: Vetical Stack Bond, tile to run vertical Trim: 12" Jolly Trim #S-1/212J Note: Tile to be installed 72"H Schluter QUADEC-K in finish AE to be used at all outside corners Hold all grout joints to minimum requirement by TCNA
CTW-4	Ceramic Tile Wall	Daltile Product: Rittenhouse Square Color: Arctic White #0190 Finish: Semi-Gloss Size: 3" x 6" Thickness: 5/16" Grout: Room #108 Laticrete Dusty Grey #60 Room #126 Laticrete Light Pewter #90 Installation Method: Subway, tile to run horizontal Note: Use Schluter RONDEC-DB in finish AE where tile does not die into wall. Hold all grout joints to minimum requirement by TCNA
FRP-1	Fiber-Reinforced Panels	Crane Composites Product: Sequentia Color: Gray #0048 Finish: Pebbled Embossed Finish #FTSTJ Size: 4' x 8' Thickness: 0.09"
GTW-1	Glass Tile Wall	American Olean Product: Color Appeal Glass + Natural Stone 3 x Random Mosaic Color: Mountain Morning Blend #C140 Size: 12" x 12" mesh sheet Grout: Laticrete Sterling Silver #78 Installation Method: Tile to run horizontal
P-1	Paint	Sherwin Williams Color: Popular Gray #SW6071 Finish: Semi-gloss Note: To be low VOC
P-2	Paint	Benjamin Moore Color: Simply White #OC-117 Finish: Semi-gloss Note: To be low VOC
P-3	Paint	Benjamin Moore Color: Chelsea Gray #HC-168 Finish: Semi-gloss Note: To be low VOC
P-4	Paint	Benjamin Moore Color: Quiet Moments #1563 Finish: Semi-gloss Note: To be low VOC

WALL CONT

ACRONYM	TYPE	DESCRIPTION
P-5	Paint	Benjamin Moore Color: Harmony Popular Gray #SW6071 Finish: Semi-gloss Note: To be low VOC
SSW-1	Stainless Steel Wall	
STW-1	Stone Tile Wall	Realstone Systems Product: Shadowstone Panel Color: Arctic White Size: 6" x 24" Thickness: .4"-1"guage Finish: Split Face

CEILING

ACRONYM	TYPE	DESCRIPTION
ACT-1	Acoustic Ceiling Tile	Armstrong Product: Dune #1775HRC Color: White (wh) Size: 24" x 24" Edge: 9/16" Beveled Tegular Suspension System: 9/16" Suprafine
EXP	Exposed Ceiling	
GYP-1	Gypsum	Painted Benjamin Moore Color: Simply White oc-117 Finish: Flat
GYP-2	Gypsum	Painted Benjamin Moore Color: Quiet Moments #1563 Finish: Flat
GYP-3	Gypsum	Painted Benjamin Moore Color: Haromny Simply White oc-117 Finish: Flat
GYP-4	Gypsum	Painted Benjamin Moore Color: Haromny Simply White oc-117 Finish: Epoxy

COUNTERTOP

ACRONYM	TYPE	DESCRIPTION
EPW-1	Epoxy Resin Worksurface	Durcon Product: Classic Countertop Color: Tan Finish: Standard Edge: Bevel Thickness:
PL-1	Plastic Laminate	Wilsonart Product: Crisp Linen #4942 Finish: Fine Velvet 38 Edge: Square Thickness: 2"
QTZ-1	Quartz	Cambria Collection: Marble Collection Product: Brittanicca Finish: Glossy Edge: Rimrock Edge (Mitered) Thickness: 3cm
SS-1	Solid Surface	Living Stone Color: Avalanche #L721 Finish: Standard Edge: Square Thickness: 3cm
SSC-1	Stainless Steel Countertop	

CABINETRY

ACRONYM	TYPE	DESCRIPTION
PL-2	Plastic Laminate	Formica Product: Citadel #1097 Finish: Matte
MW-1	Millwork	Custom paint grade poplar w/ raised panels Note: To be painted P-3 Reference elevations and details for design
SSM-1	Stainless Steel Millwork	

DAMMON ENGINEERING, INC.
LOUISIANA & MISSISSIPPI
www.dammonengineering.com
info@dammonengineering.com
PH: 985.649.5832
Chief Engineer: Brian Mistich, PE
554 Old Spanish Trail
Slidell, LA 70458

REVISIONS

#	DESCRIPTION	DATE

SEAL:

PROGRESS SET

NEW MEDICAL OFFICE
DIANA OAK HARBOR REAL ESTATE LLC
540 OAK HARBOR BLVD
SLIDELL, LA 70458

JOB No:	2513	DATE:	06-03-2025
DRAWN BY:	CAD	CHECKED BY:	JMS

The drawings, specifications and other documents prepared by Dammon Engineering, Inc. for this project are instruments of service for use solely with respect to this project. All reproductions, publications or other uses of or disclosure of such documents without the written consent of Dammon Engineering, Inc. are prohibited. Dammon Engineering, Inc. retains all rights in and to such documents.

SHEET TITLE:
FINISH SCHEDULE AND FINISH LEGEND

DRAWING NUMBER:
A2.0