PANEL SCHEDULE

PANEL: P31
LOCATION: MECHANICAL, ELECTRICAL, & PLUMBING ROOM 209 SECOND LEVEL
FEEDER SOURCE: MDP PANEL
VOLTAGE: 208/120V, 400A, 3Φ, 4W W/MLO
ENCLOSURE: SURFACE MOUNTED W/ EQUIPMENT GND BAR SQ D TYPE NQ PANELBOARD

CKT NO	THHN WIRE SIZE	LOAD DESCRIPTION LOCATION	BREAKER AMP	BREAKER POLE	LOAD (VA)	LOAD (VA)	BREAKER POLE	BREAKER AMP	LOAD DESCRIPTION LOCATION	THHN WIRE SIZE	CKT NO
1	#12	DEDICATED RECEPTACLE NEAR STAIRS, OPPOSITE END OF BUILDING	20	1	1500	720	1	20	RECEPTACLES, MAINT. ROOM AT OPPOSITE END OF BUILDING AND HALLWAY	#12	2
3	#12	DEDICATED RECEPTACLE NEAR STAIRS, OPPOSITE END OF BUILDING	20	1	1500	720	1	20	RECEPTACLES, LAUNDRY ROOM HOUSEKEEPING AND HALLWAY	#12	4
5		SPARE	20	1		180	1	20	RECEPTACLE, THIS ROOM	#12	6
7		SPARE	20	1		315	1	20	LIGHTING, THIS END OF HALL	#12	8
9		SPARE	20	1		315	1	20	LIGHTING, THIS EQUIPMENT ROOM	#12	10
11		SPARE	20	1		434	1	20	LIGHTING, HOUSEKEEPING, LAUNDRY AND ELEVATOR LOBBY	#12	12
13		SPARE	20	1		512	1	20	LIGHTS, CENTER OF HALL	#12	14
15	#12	ATTIC LIGHT AND RECEPTACLE	20	1	1000	644	1	20	LIGHTING, OPPOSITE END OF HALLWAY	#12	16
17		SPARE	20	1		628	1	20	LIGHTING, MAINTENANCE ROOM OPPOSITE END OF BUILDING	#12	18
19					19820	1000	1	20	ATTIC LIGHT AND RECEPTACLE	#12	20
21	#4/0	PANEL P32	175	3	20680	1000	1	20	ATTIC LIGHT AND RECEPTACLE	#12	22
23					19000	1000	1	20	ATTIC LIGHT AND RECEPTACLE	#12	24
25					18070	1000	1	20	ATTIC LIGHT AND RECEPTACLE	#12	26
27	#4/0	PANEL P33	200	3	18930	1000	1	20	ATTIC LIGHT AND RECEPTACLE	#12	28
29					19000		1	20	SPARE		30
31					18070	3333					32
33	#4/0	PANEL P34	200	3	18930	3333	3	60	2 1/2 TON HVAC UNIT, 3RD LEVEL 10 KW HEAT	#6	34
35					19000	3333					36
37					18070	18070					38
39	#4/0	PANEL P35	175	3	18930	18930	3	175	PANEL P36	#4/0	40
41					19000	19000					42

SOLID NEUTRAL NEUTRAL WIRE (N) | TOTAL CONNECTED LOAD (VA) = 306,967 | GROUND BUS GROUND WIRE (G)

AΦ =100,480 | BΦ = 105,912 | CΦ = 100,575

PANEL SCHEDULE

PANEL: P33
LOCATION: MECHANICAL, ELECTRICAL, & PLUMBING ROOM 309 THIRD LEVEL
FEEDER SOURCE: MDP PANEL
VOLTAGE: 208/120V, 200A, 3Φ, 4W W/MLO
ENCLOSURE: SURFACE MOUNTED W/ EQUIPMENT GND BAR SQ D TYPE QO LOAD CENTER

CKT NO	THHN WIRE SIZE	LOAD DESCRIPTION LOCATION	BREAKER AMP	BREAKER POLE	LOAD (VA)	LOAD (VA)	BREAKER POLE	BREAKER AMP	LOAD DESCRIPTION LOCATION	THHN WIRE SIZE	CKT NO
1	#10	COOK TOP TWO BURNER, SUITE 306	30	1	2400	0	1	20	SPARE	#12	2
3	#10	COOK TOP TWO BURNER, SUITE 307	30	1	2400	0	1	20	SPARE	#12	4
5	#10	COOK TOP TWO BURNER, SUITE 310	30	1	2400	1500	1	20	REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 310	#12	6
7	#10	COOK TOP TWO BURNER, SUITE 311	30	1	2400	1000	1	20	MICROWAVE OVEN, SUITE 310	#12	8
9	#10	COOK TOP TWO BURNER, SUITE 312	30	1	2400	1000	1	20	DISH WASHER AND GARBAGE DISPOSAL, SUITE 310	#12	10
11	#12	REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 306	20	1	1500	1080	1	20	RECEPTACLES AND LIGHTING, SUITE 310	#12	12
13	#12	MICROWAVE OVEN, SUITE 306	20	1	1000	720	1	20	BATHROOM RECEPTACLES AND LIGHTING SUITE 310	#12	14
15	#12	DISH WASHER AND GARBAGE DISPOSAL, SUITE 306	20	1	1000	1500	1	20	REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 311	#12	16
17	#12	RECEPTACLES AND LIGHTING, SUITE 306	20	1	1080	1000	1	20	MICROWAVE OVEN, SUITE 311	#12	18
19	#12	BATHROOM RECEPTACLES AND LIGHTING SUITE 306	20	1	720	1000	1	20	DISH WASHER AND GARBAGE DISPOSAL, SUITE 311	#12	20
21	#12	REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 307	20	1	1500	1080	1	20	RECEPTACLES AND LIGHTING, SUITE 311	#12	22
23	#12	MICROWAVE OVEN, SUITE 307	20	1	1000	720	1	20	BATHROOM RECEPTACLES AND LIGHTING SUITE 311	#12	24
25	#12	DISH WASHER AND GARBAGE DISPOSAL, SUITE 307	20	1	1000	1500	1	20	REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 312	#12	26
27	#12	RECEPTACLES AND LIGHTING, SUITE 307	20	1	1080	1000	1	20	MICROWAVE OVEN, SUITE 312	#12	28
29	#12	BATHROOM RECEPTACLES AND LIGHTING SUITE 307	20	1	720	1000	1	20	DISH WASHER AND GARBAGE DISPOSAL, SUITE 312	#12	30
31	#12	SUITE 306 PTAC 208V RECEPTACLE	20	2	1750	1080	1	20	RECEPTACLES AND LIGHTING, SUITE 312	#12	32
33					1750	720	1	20	BATHROOM RECEPTACLES AND LIGHTING SUITE 312	#12	34
35	#12	SUITE 307 PTAC 208V RECEPTACLE	20	2	1750	1750	2	20	SUITE 311 PTAC 208V RECEPTACLE	#12	36
37					1750	1750					38
39	#12	SUITE 310 PTAC 208V RECEPTACLE	20	2	1750	1750	2	20	SUITE 312 PTAC 208V RECEPTACLE	#12	40
41					1750	1750					42

SOLID NEUTRAL NEUTRAL WIRE (N) | TOTAL CONNECTED LOAD (VA) = 56,000 | GROUND BUS GROUND WIRE (G)

AΦ = 18,070 | BΦ = 18,930 | CΦ = 19,000

PANEL SCHEDULE

PANEL: P35
LOCATION: MECHANICAL, ELECTRICAL, & PLUMBING ROOM 309 THIRD LEVEL
FEEDER SOURCE: MDP PANEL
VOLTAGE: 208/120V, 200A, 3Φ, 4W W/MLO
ENCLOSURE: SURFACE MOUNTED W/ EQUIPMENT GND BAR SQ D TYPE QO LOAD CENTER

CKT NO	THHN WIRE SIZE	LOAD DESCRIPTION LOCATION	BREAKER AMP	BREAKER POLE	LOAD (VA)	LOAD (VA)	BREAKER POLE	BREAKER AMP	LOAD DESCRIPTION LOCATION	THHN WIRE SIZE	CKT NO
1	#10	COOK TOP TWO BURNER, SUITE 320	30	1	2400	0	1	20	SPARE	#12	2
3	#10	COOK TOP TWO BURNER, SUITE 321	30	1	2400	0	1	20	SPARE	#12	4
5	#10	COOK TOP TWO BURNER, SUITE 322	30	1	2400	1500	1	20	REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 322	#12	6
7	#10	COOK TOP TWO BURNER, SUITE 323	30	1	2400	1000	1	20	MICROWAVE OVEN, SUITE 322	#12	8
9	#10	COOK TOP TWO BURNER, SUITE 327	30	1	2400	1000	1	20	DISH WASHER AND GARBAGE DISPOSAL, SUITE 322	#12	10
11	#12	REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 320	20	1	1500	1080	1	20	RECEPTACLES AND LIGHTING, SUITE 322	#12	12
13	#12	MICROWAVE OVEN, SUITE 320	20	1	1000	720	1	20	BATHROOM RECEPTACLES AND LIGHTING SUITE 322	#12	14
15	#12	DISH WASHER AND GARBAGE DISPOSAL, SUITE 320	20	1	1000	1500	1	20	REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 323	#12	16
17	#12	RECEPTACLES AND LIGHTING, SUITE 320	20	1	1080	1000	1	20	MICROWAVE OVEN, SUITE 323	#12	18
19	#12	BATHROOM RECEPTACLES AND LIGHTING SUITE 320	20	1	720	1000	1	20	DISH WASHER AND GARBAGE DISPOSAL, SUITE 323	#12	20
21	#12	REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 321	20	1	1500	1080	1	20	RECEPTACLES AND LIGHTING, SUITE 323	#12	22
23	#12	MICROWAVE OVEN, SUITE 321	20	1	1000	720	1	20	BATHROOM RECEPTACLES AND LIGHTING SUITE 323	#12	24
25	#12	DISH WASHER AND GARBAGE DISPOSAL, SUITE 321	20	1	1000	1500	1	20	REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 327	#12	26
27	#12	RECEPTACLES AND LIGHTING, SUITE 321	20	1	1080	1000	1	20	MICROWAVE OVEN, SUITE 327	#12	28
29	#12	BATHROOM RECEPTACLES AND LIGHTING SUITE 321	20	1	720	1000	1	20	DISH WASHER AND GARBAGE DISPOSAL, SUITE 327	#12	30
31	#12	SUITE 320 PTAC 208V RECEPTACLE	20	2	1750	1080	1	20	RECEPTACLES AND LIGHTING, SUITE 327	#12	32
33					1750	720	1	20	BATHROOM RECEPTACLES AND LIGHTING SUITE 327	#12	34
35	#12	SUITE 321 PTAC 208V RECEPTACLE	20	2	1750	1750	2	20	SUITE 323 PTAC 208V RECEPTACLE	#12	36
37					1750	1750					38
39	#12	SUITE 322 PTAC 208V RECEPTACLE	20	2	1750	1750	2	20	SUITE 327 PTAC 208V RECEPTACLE	#12	40
41					1750	1750					42

SOLID NEUTRAL NEUTRAL WIRE (N) | TOTAL CONNECTED LOAD (VA) = 56,000 | GROUND BUS GROUND WIRE (G)

AΦ = 18,070 | BΦ = 18,930 | CΦ = 19,000

PANEL SCHEDULE

PANEL: P32
LOCATION: MECHANICAL, ELECTRICAL, & PLUMBING ROOM 309 THIRD LEVEL
FEEDER SOURCE: MDP PANEL
VOLTAGE: 208/120V, 200A, 3Φ, 4W W/MLO
ENCLOSURE: SURFACE MOUNTED W/ EQUIPMENT GND BAR SQ D TYPE QO LOAD CENTER

CKT NO	THHN WIRE SIZE	LOAD DESCRIPTION LOCATION	BREAKER AMP	BREAKER POLE	LOAD (VA)	LOAD (VA)	BREAKER POLE	BREAKER AMP	LOAD DESCRIPTION LOCATION	THHN WIRE SIZE	CKT NO
1	#10	COOK TOP TWO BURNER, SUITE 301	30	1	2400	1500	1	20	REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 303	#12	2
3	#10	COOK TOP TWO BURNER, SUITE 302	30	1	2400	1000	1	20	MICROWAVE OVEN, SUITE 303	#12	4
5	#10	COOK TOP TWO BURNER, SUITE 303	30	1	2400	1000	1	20	DISH WASHER AND GARBAGE DISPOSAL, SUITE 303	#12	6
7	#10	COOK TOP TWO BURNER, SUITE 304	30	1	2400	1080	1	20	RECEPTACLES AND LIGHTING, SUITE 303	#12	8
9	#10	COOK TOP TWO BURNER, SUITE 305	30	1	2400	720	1	20	BATHROOM RECEPTACLES AND LIGHTING SUITE 303	#12	10
11	#12	REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 301	20	1	1500	1500	1	20	REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 304	#12	12
13	#12	MICROWAVE OVEN, SUITE 301	20	1	1000	1000	1	20	MICROWAVE OVEN, SUITE 304	#12	14
15	#12	DISH WASHER AND GARBAGE DISPOSAL, SUITE 301	20	1	1000	1000	1	20	DISH WASHER AND GARBAGE DISPOSAL, SUITE 304	#12	16
17	#12	RECEPTACLES AND LIGHTING, SUITE 301	20	1	1080	1080	1	20	RECEPTACLES AND LIGHTING, SUITE 304	#12	18
19	#12	BATHROOM RECEPTACLES AND LIGHTING SUITE 301	20	1	720	720	1	20	BATHROOM RECEPTACLES AND LIGHTING SUITE 304	#12	20
21	#12	REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 302	20	1	1500	1500	1	20	REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 305	#12	22
23	#12	MICROWAVE OVEN, SUITE 302	20	1	1000	1000	1	20	MICROWAVE OVEN, SUITE 305	#12	24
25	#12	DISH WASHER AND GARBAGE DISPOSAL, SUITE 302	20	1	1000	1000	1	20	DISH WASHER AND GARBAGE DISPOSAL, SUITE 305	#12	26
27	#12	RECEPTACLES AND LIGHTING, SUITE 302	20	1	1080	1080	1	20	RECEPTACLES AND LIGHTING, SUITE 305	#12	28
29	#12	BATHROOM RECEPTACLES AND LIGHTING SUITE 302	20	1	720	720	1	20	BATHROOM RECEPTACLES AND LIGHTING SUITE 305	#12	30
31	#12	SUITE 301 PTAC 208V RECEPTACLE	20	2	1750	1750	2	20	SUITE 303 PTAC, 208V RECEPTACLE IN BEDROOM	#12	32
33					1750	1750					34
35	#12	SUITE 302 PTAC 208V RECEPTACLE	20	2	1750	1750	2	20	SUITE 304 PTAC 208V RECEPTACLE	#12	36
37					1750	1750					38
39	#12	SUITE 303 PTAC 208V RECEPTACLE IN LIVING ROOM	20	2	1750	1750	2	20	SUITE 305 PTAC 208V RECEPTACLE	#12	40
41					1750	1750					42

SOLID NEUTRAL NEUTRAL WIRE (N) | TOTAL CONNECTED LOAD (VA) = 59,500 | GROUND BUS GROUND WIRE (G)

AΦ = 19,820 | BΦ = 20,680 | CΦ = 19,000

PANEL SCHEDULE

PANEL: P34
LOCATION: MECHANICAL, ELECTRICAL, & PLUMBING ROOM 309 THIRD LEVEL
FEEDER SOURCE: MDP PANEL
VOLTAGE: 208/120V, 200A, 3Φ, 4W W/MLO
ENCLOSURE: SURFACE MOUNTED W/ EQUIPMENT GND BAR SQ D TYPE QO LOAD CENTER

CKT NO	THHN WIRE SIZE	LOAD DESCRIPTION LOCATION	BREAKER AMP	BREAKER POLE	LOAD (VA)	LOAD (VA)	BREAKER POLE	BREAKER AMP	LOAD DESCRIPTION LOCATION	THHN WIRE SIZE	CKT NO
1	#10	COOK TOP TWO BURNER, SUITE 313	30	1	2400	0	1	20	SPARE	#12	2
3	#10	COOK TOP TWO BURNER, SUITE 316	30	1	2400	0	1	20	SPARE	#12	4
5	#10	COOK TOP TWO BURNER, SUITE 317	30	1	2400	1500	1	20	REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 317	#12	6
7	#10	COOK TOP TWO BURNER, SUITE 318	30	1	2400	1000	1	20	MICROWAVE OVEN, SUITE 317	#12	8
9	#10	COOK TOP TWO BURNER, SUITE 319	30	1	2400	1000	1	20	DISH WASHER AND GARBAGE DISPOSAL, SUITE 317	#12	10
11	#12	REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 313	20	1	1500	1080	1	20	RECEPTACLES AND LIGHTING, SUITE 317	#12	12
13	#12	MICROWAVE OVEN, SUITE 313	20	1	1000	720	1	20	BATHROOM RECEPTACLES AND LIGHTING SUITE 317	#12	14
15	#12	DISH WASHER AND GARBAGE DISPOSAL, SUITE 313	20	1	1000	1500	1	20	REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 318	#12	16
17	#12	RECEPTACLES AND LIGHTING, SUITE 313	20	1	1080	1000	1	20	MICROWAVE OVEN, SUITE 318	#12	18
19	#12	BATHROOM RECEPTACLES AND LIGHTING SUITE 313	20	1	720	1000	1	20	DISH WASHER AND GARBAGE DISPOSAL, SUITE 318	#12	20
21	#12	REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 316	20	1	1500	1080	1	20	RECEPTACLES AND LIGHTING, SUITE 318	#12	22
23	#12	MICROWAVE OVEN, SUITE 316	20	1	1000	720	1	20	BATHROOM RECEPTACLES AND LIGHTING SUITE 318	#12	24
25	#12	DISH WASHER AND GARBAGE DISPOSAL, SUITE 316	20	1	1000	1500	1	20	REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 319	#12	26
27	#12	RECEPTACLES AND LIGHTING, SUITE 316	20	1	1080	1000	1	20	MICROWAVE OVEN, SUITE 319	#12	28
29	#12	BATHROOM RECEPTACLES AND LIGHTING SUITE 316	20	1	720	1000	1	20	DISH WASHER AND GARBAGE DISPOSAL, SUITE 319	#12	30
31	#12	SUITE 313 PTAC 208V RECEPTACLE	20	2	1750	1080	1	20	RECEPTACLES AND LIGHTING, SUITE 319	#12	32
33					1750	720	1	20	BATHROOM RECEPTACLES AND LIGHTING SUITE 319	#12	34
35	#12	SUITE 316 PTAC 208V RECEPTACLE	20	2	1750	1750	2	20	SUITE 318 PTAC 208V RECEPTACLE	#12	36
37					1750	1750					38
39	#12	SUITE 317 PTAC 208V RECEPTACLE	20	2	1750	1750	2	20	SUITE 319 PTAC 208V RECEPTACLE	#12	40
41					1750	1750					42

SOLID NEUTRAL NEUTRAL WIRE (N) | TOTAL CONNECTED LOAD (VA) = 56,000 | GROUND BUS GROUND WIRE (G)

AΦ = 18,070 | BΦ = 18,930 | CΦ = 19,000

PANEL SCHEDULE

PANEL: P36
LOCATION: MECHANICAL, ELECTRICAL, & PLUMBING ROOM 309 THIRD LEVEL
FEEDER SOURCE: MDP PANEL
VOLTAGE: 208/120V, 200A, 3Φ, 4W W/MLO
ENCLOSURE: SURFACE MOUNTED W/ EQUIPMENT GND BAR SQ D TYPE QO LOAD CENTER

CKT NO	THHN WIRE SIZE	LOAD DESCRIPTION LOCATION	BREAKER AMP	BREAKER POLE	LOAD (VA)	LOAD (VA)	BREAKER POLE	BREAKER AMP	LOAD DESCRIPTION LOCATION	THHN WIRE SIZE	CKT NO
1	#10	COOK TOP TWO BURNER, SUITE 328	30	1	2400	0	1	20	SPARE	#12	2
3	#10	COOK TOP TWO BURNER, SUITE 329	30	1	2400	0	1	20	SPARE	#12	4
5	#10	COOK TOP TWO BURNER, SUITE 330	30	1	2400	1500	1	20	REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 330	#12	6
7	#10	COOK TOP TWO BURNER, SUITE 331	30	1	2400	1000	1	20	MICROWAVE OVEN, SUITE 330	#12	8
9	#10	COOK TOP TWO BURNER, SUITE 332	30	1	2400	1000	1	20	DISH WASHER AND GARBAGE DISPOSAL, SUITE 330	#12	10
11	#12	REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 328	20	1	1500	1080	1	20	RECEPTACLES AND LIGHTING, SUITE 330	#12	12
13	#12	MICROWAVE OVEN, SUITE 328	20	1	1000	720	1	20	BATHROOM RECEPTACLES AND LIGHTING SUITE 330	#12	14
15	#12	DISH WASHER AND GARBAGE DISPOSAL, SUITE 328	20	1	1000	1500	1	20	REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 331	#12	16
17	#12	RECEPTACLES AND LIGHTING, SUITE 328	20	1	1080	1000	1	20	MICROWAVE OVEN, SUITE 331	#12	18
19	#12	BATHROOM RECEPTACLES AND LIGHTING SUITE 328	20	1	720	1000	1	20	DISH WASHER AND GARBAGE DISPOSAL, SUITE 331	#12	20
21	#12	REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 328	20	1	1500	1080	1	20	RECEPTACLES AND LIGHTING, SUITE 331	#12	22
23	#12	MICROWAVE OVEN, SUITE 329	20	1	1000	720	1	20	BATHROOM RECEPTACLES AND LIGHTING SUITE 331	#12	24
25	#12	DISH WASHER AND GARBAGE DISPOSAL, SUITE 329	20	1	1000	1500	1	20	REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 332	#12	26
27	#12	RECEPTACLES AND LIGHTING, SUITE 329	20	1	1080	1000	1	20	MICROWAVE OVEN, SUITE 332	#12	28
29	#12	BATHROOM RECEPTACLES AND LIGHTING SUITE 329	20	1	720	1000	1	20	DISH WASHER AND GARBAGE DISPOSAL, SUITE 332	#12	30
31	#12	SUITE 328 PTAC 208V RECEPTACLE	20	2	1750	1080	1	20	RECEPTACLES AND LIGHTING, SUITE 332	#12	32
33					1750	720	1	20	BATHROOM RECEPTACLES AND LIGHTING SUITE 332	#12	34
35	#12	SUITE 329 PTAC 208V RECEPTACLE	20	2	1750	1750	2	20	SUITE 331 PTAC 208V RECEPTACLE	#12	36
37					1750	1750					38
39	#12	SUITE 330 PTAC 208V RECEPTACLE	20	2	1750	1750	2	20	SUITE 332 PTAC 208V RECEPTACLE	#12	40
41					1750	1750					42

SOLID NEUTRAL NEUTRAL WIRE (N) | TOTAL CONNECTED LOAD (VA) = 56,000 | GROUND BUS GROUND WIRE (G)

AΦ = 18,070 | BΦ = 18,930 | CΦ = 19,000

DAMMON ENGINEERING, INC.
LOUISIANA & MISSISSIPPI
Chief Engineer: Brian Mistich, PE
554 Old Spanish Trail
Slidell, LA 70458
www.dammonengineering.com
info@dammonengineering.com
PH: 985.649.5832 F: 985.641.5950

REVISIONS

#	DESCRIPTION	DATE

SEAL: STATE OF LOUISIANA — BRIAN A. MISTICH, License No. 30187, PROFESSIONAL ENGINEER — 02-19-16

MAIN STAY SUITES
700 MAIN STREET
LOT #7 LA HWY 27
HACKBERRY, LA 70645

JOB No: 2265 | DATE: FEBRUARY, 2016
DRAWN BY: DD/JTL | CHECKED BY: BAM

The above drawings and specifications, designs and arrangements represented thereby are and shall remain the property of Dammon Engineering, and no part thereof shall be copied, disclosed to others, or used in connection with any work or project other than the specific project for which the have been prepared and developed without written consent of Dammon Engineering. Visual contact with these drawings or specifications shall constitute conclusive evidence of acceptance of these restrictions.

SHEET TITLE: ELECTRICAL PANEL SCHEDULES, THIRD FLOOR

DRAWING NUMBER: E108