# PANEL SCHEDULE

PANEL: P12
LOCATION: MECHANICAL, ELECTRICAL, & PLUMBING ROOM 114 FIRST LEVEL
FEEDER SOURCE: MDP PANEL
VOLTAGE: 208/120V, 200A, 3Φ, 4W W/MLO
ENCLOSURE: SURFACE MOUNTED W/ EQUIPMENT GND BAR SQ D TYPE QO LOAD CENTER

| CKT NO | THHN WIRE SIZE | LOAD DESCRIPTION LOCATION | BREAKER AMP | BREAKER POLE | LOAD (VA) | LOAD (VA) | BREAKER POLE | BREAKER AMP | LOAD DESCRIPTION LOCATION | THHN WIRE SIZE | CKT NO |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | #12 | RECEPTACLES AT THE REGISTRATION DESK | 20 | 1 | 360 | 1000 | 1 | 20 | RECEPTACLES, VESTIBULE AND WORK ROOM | #12 | 2 |
| 3 | #12 | RECEPTACLES AT THE REGISTRATION DESK | 20 | 1 | 360 | 1500 | 1 | 20 | DEDICATED RECEPTACLE, COMMUNITY ROOM | #12 | 4 |
| 5 | #12 | RECEPTACLES RECEPTION ROOM, STORE AND CORRIDOR | 20 | 1 | 720 | 1080 | 1 | 20 | RECEPTACLES, RIGHT SIDE OF COMMUNITY ROOM & PORCH | #12 | 6 |
| 7 | #12 | RECEPTACLES MANAGERS OFFICE AND STORE | 20 | 1 | 1080 | 400 | 1 | 20 | RECEPTACLES, LEFT SIDE OF COMMUNITY ROOM & PORCH | #12 | 8 |
| 9 | #12 | RECEPTACLES LINEN, LAUNDRY AND BREAK ROOM | 20 | 1 | 720 | 360 | 1 | 20 | RECEPTACLES, AT SINK IN PANTRY ROOM | #12 | 10 |
| 11 | #12 | RECEPTACLES LAUNDRY, MECHANICAL ROOM AND CORRIDOR | 20 | 1 | 720 | 360 | 1 | 20 | RECEPTACLE, DRY COUNTER IN PANTRY ROOM | #12 | 12 |
| 13 | #12 | DEDICATED RECEPTACLE, WORK ROOM | 20 | 1 | 720 | 1500 | 1 | 20 | DEDICATED RECEPTACLE, PANTRY ROOM | #12 | 14 |
| 15 | #12 | EXHAUST FAN IN SHOWER | 20 | 1 | 500 | 1500 | 1 | 20 | DEDICATED RECEPTACLE, PANTRY ROOM | #12 | 16 |
| 17 | #12 | GAS WATER HEATER IGNITER FOR WATER HEATER #1 | 20 | 1 | 500 | 1500 | 1 | 20 | DRINKING FOUNTAIN IN CORRIDOR | #12 | 18 |
| 19 | #12 | GAS WATER HEATER IGNITER FOR WATER HEATER #2 | 20 | 1 | 500 | 1800 | 1 | 20 | ELEVATOR CONTROLS POWER | #12 | 20 |
| 21 | #12 | RECEPTACLES, THIS ROOM, WATER HEATER ROOM AND A/C EQUIP. | 20 | 1 | 500 | 1500 | 1 | 20 | DEDICATED GFI RECEPTACLE IN ELEVATOR EQUIPMENT ROOM | #12 | 22 |
| 23 | #12 | LIGHTING, THIS ROOM, WATER HEATER ROOM, THIS END OF HALLWAY | 20 | 1 | 984 | 1500 | 1 | 20 | RECEPTACLE IN ELEVATOR PIT | #12 | 24 |
| 25 | #12 | LIGHTING, LINEN, LAUNDRY ROOM AND BREAK ROOM | 20 | 1 | 847 | 2500 | 2 | 30 | GUEST DRYER | #10 | 26 |
| 27 | #12 | LIGHTING, ELEVATOR EQUIPMENT ROOM, PIT, AND ELEVATOR LOBBY | 20 | 1 | 847 | 2500 | | | | | 28 |
| 29 | #12 | LIGHTING, GUEST LAUNDRY, MECHANICAL ROOM, MANAGERS SUITE, STORE | 20 | 1 | 847 | 2500 | 2 | 30 | GUEST DRYER | #10 | 30 |
| 31 | #12 | LIGHTING, REAR PORCH | 20 | 1 | 736 | 2500 | | | | | 32 |
| 33 | #12 | LIGHTING, COMMUNITY ROOM, PANTRY, PORCH CHAIRS | 20 | 1 | 912 | 1500 | 1 | 20 | GUEST WASHER | #12 | 34 |
| 35 | #12 | LIGHTING, COVERED PORCH AND ENTRY | 20 | 1 | 1814 | 1500 | 1 | 20 | GUEST WASHER | #12 | 36 |
| 37 | #12 | LIGHTING, LOBBY, WORKROOM, VESTIBULE AND RECEPTION AREA | 20 | 1 | 781 | 1500 | 1 | 20 | GUEST WASHER | #12 | 38 |
| 39 | #12 | SIGN LIGHTING | 20 | 1 | 1000 | | 1 | 20 | SPARE | | 40 |
| 41 | | SPARE | 20 | 1 | | | 1 | 20 | SPARE | | 42 |

SOLID NEUTRAL NEUTRAL WIRE (N) — TOTAL CONNECTED LOAD (VA) = 44,468 — GROUND BUS GROUND WIRE (G)
AΦ = 16,744 BΦ = 13,699 CΦ = 14,025

# PANEL SCHEDULE

PANEL: P14
LOCATION: MECHANICAL, ELECTRICAL, & PLUMBING ROOM 114 FIRST LEVEL
FEEDER SOURCE: MDP PANEL
VOLTAGE: 208/120V, 200A, 3Φ, 4W W/MLO
ENCLOSURE: SURFACE MOUNTED W/ EQUIPMENT GND BAR SQ D TYPE QO LOAD CENTER

| CKT NO | THHN WIRE SIZE | LOAD DESCRIPTION LOCATION | BREAKER AMP | BREAKER POLE | LOAD (VA) | LOAD (VA) | BREAKER POLE | BREAKER AMP | LOAD DESCRIPTION LOCATION | THHN WIRE SIZE | CKT NO |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | #10 | COOK TOP TWO BURNER, SUITE 110 | 30 | 1 | 2400 | 0 | 1 | 20 | SPARE | #12 | 2 |
| 3 | #10 | COOK TOP TWO BURNER, SUITE 112 | 30 | 1 | 2400 | 0 | 1 | 20 | SPARE | #12 | 4 |
| 5 | #10 | COOK TOP TWO BURNER, SUITE 116 | 30 | 1 | 2400 | 1500 | 1 | 20 | REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 111 | #12 | 6 |
| 7 | #10 | COOK TOP TWO BURNER, SUITE 111 | 30 | 1 | 2400 | 1000 | 1 | 20 | MICROWAVE OVEN, SUITE 111 | #12 | 8 |
| 9 | #10 | COOK TOP TWO BURNER, SUITE 115 | 30 | 1 | 2400 | 1000 | 1 | 20 | DISH WASHER AND GARBAGE DISPOSAL, SUITE 111 | #12 | 10 |
| 11 | #12 | REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 110 | 20 | 1 | 1500 | 1080 | 1 | 20 | RECEPTACLES AND LIGHTING, SUITE 111 | #12 | 12 |
| 13 | #12 | MICROWAVE OVEN, SUITE 110 | 20 | 1 | 1000 | 720 | 1 | 20 | BATHROOM RECEPTACLES AND LIGHTING SUITE 111 | #12 | 14 |
| 15 | #12 | DISH WASHER AND GARBAGE DISPOSAL, SUITE 110 | 20 | 1 | 1000 | 1500 | 1 | 20 | REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 115 | #12 | 16 |
| 17 | #12 | RECEPTACLES AND LIGHTING, SUITE 110 | 20 | 1 | 1080 | 1000 | 1 | 20 | MICROWAVE OVEN, SUITE 115 | #12 | 18 |
| 19 | #12 | BATHROOM RECEPTACLES AND LIGHTING SUITE 110 | 20 | 1 | 720 | 1000 | 1 | 20 | DISH WASHER AND GARBAGE DISPOSAL, SUITE 115 | #12 | 20 |
| 21 | #12 | REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 112 | 20 | 1 | 1500 | 1080 | 1 | 20 | RECEPTACLES AND LIGHTING, SUITE 115 | #12 | 22 |
| 23 | #12 | MICROWAVE OVEN, SUITE 112 | 20 | 1 | 1000 | 720 | 1 | 20 | BATHROOM RECEPTACLES AND LIGHTING SUITE 115 | #12 | 24 |
| 25 | #12 | DISH WASHER AND GARBAGE DISPOSAL, SUITE 112 | 20 | 1 | 1000 | 1500 | 1 | 20 | REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 116 | #12 | 26 |
| 27 | #12 | RECEPTACLES AND LIGHTING, SUITE 112 | 20 | 1 | 1080 | 1000 | 1 | 20 | MICROWAVE OVEN, SUITE 116 | #12 | 28 |
| 29 | #12 | BATHROOM RECEPTACLES AND LIGHTING SUITE 112 | 20 | 1 | 720 | 1000 | 1 | 20 | DISH WASHER AND GARBAGE DISPOSAL, SUITE 116 | #12 | 30 |
| 31 | #12 | SUITE 110 PTAC 208V RECEPTACLE | 20 | 2 | 1750 | 1080 | 1 | 20 | RECEPTACLES AND LIGHTING, SUITE 116 | #12 | 32 |
| 33 | | | | | 1750 | 720 | 1 | 20 | BATHROOM RECEPTACLES AND LIGHTING SUITE 116 | #12 | 34 |
| 35 | #12 | SUITE 112 PTAC 208V RECEPTACLE | 20 | 2 | 1750 | 1750 | 2 | 20 | SUITE 111 PTAC 208V RECEPTACLE | #12 | 36 |
| 37 | | | | | 1750 | 1750 | | | | | 38 |
| 39 | #12 | SUITE 116 PTAC 208V RECEPTACLE | 20 | 2 | 1750 | 1750 | 2 | 20 | SUITE 115 PTAC 208V RECEPTACLE | #12 | 40 |
| 41 | | | | | 1750 | 1750 | | | | | 42 |

SOLID NEUTRAL NEUTRAL WIRE (N) — TOTAL CONNECTED LOAD (VA) =56,000 — GROUND BUS GROUND WIRE (G)
AΦ = 18,070 BΦ = 18,930 CΦ = 19,000

# PANEL SCHEDULE

PANEL: P16
LOCATION: MECHANICAL, ELECTRICAL, & PLUMBING ROOM 114 FIRST LEVEL
FEEDER SOURCE: MDP PANEL
VOLTAGE: 208/120V, 200A, 3Φ, 4W W/MLO
ENCLOSURE: SURFACE MOUNTED W/ EQUIPMENT GND BAR SQ D TYPE QO LOAD CENTER

| CKT NO | THHN WIRE SIZE | LOAD DESCRIPTION LOCATION | BREAKER AMP | BREAKER POLE | LOAD (VA) | LOAD (VA) | BREAKER POLE | BREAKER AMP | LOAD DESCRIPTION LOCATION | THHN WIRE SIZE | CKT NO |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | #12 | SUITE 138 PTAC 208V RECEPTACLE | 20 | 2 | 1750 | 1500 | 1 | 20 | REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 133 | #12 | 2 |
| 3 | | | | | 1750 | 1000 | 1 | 20 | MICROWAVE OVEN, SUITE 133 | #12 | 4 |
| 5 | #12 | SUITE 139 PTAC 208V RECEPTACLE | 20 | 2 | 1750 | 1000 | 1 | 20 | DISH WASHER AND GARBAGE DISPOSAL, SUITE 133 | #12 | 6 |
| 7 | | | | | 1750 | 1080 | 1 | 20 | RECEPTACLES AND LIGHTING, SUITE 133 | #12 | 8 |
| 9 | #10 | COOK TOP TWO BURNER, SUITE 134 | 30 | 1 | 2400 | 720 | 1 | 20 | BATHROOM RECEPTACLES AND LIGHTING SUITE 133 | #12 | 10 |
| 11 | #10 | COOK TOP TWO BURNER, SUITE 135 | 30 | 1 | 2400 | 1500 | 1 | 20 | REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 133 | #12 | 12 |
| 13 | | | | | | 1000 | 1 | 20 | MICROWAVE OVEN, SUITE 133 | #12 | 14 |
| 15 | | | | | | 1000 | 1 | 20 | DISH WASHER AND GARBAGE DISPOSAL, SUITE 133 | #12 | 16 |
| 17 | | | | | | 1080 | 1 | 20 | RECEPTACLES AND LIGHTING, SUITE 133 | #12 | 18 |
| 19 | | | | | | 720 | 1 | 20 | BATHROOM RECEPTACLES AND LIGHTING SUITE 133 | #12 | 20 |
| 21 | | | | | | | | | | | 22 |
| 23 | | | | | | | | | | | 24 |
| 25 | | | | | | | | | | | 26 |
| 27 | | | | | | | | | | | 28 |
| 29 | | | | | | | | | | | 30 |
| 31 | | | | | | | | | | | 32 |
| 33 | | | | | | | | | | | 34 |
| 35 | | | | | | | | | | | 36 |
| 37 | | | | | | | | | | | 38 |
| 39 | | | | | | | | | | | 40 |
| 41 | | | | | | | | | | | 42 |

SOLID NEUTRAL NEUTRAL WIRE (N) — TOTAL CONNECTED LOAD (VA) = 22,400 — GROUND BUS GROUND WIRE (G)
AΦ = 7,800 BΦ = 6,870 CΦ = 7,730

# PANEL SCHEDULE

PANEL: P13
LOCATION: MECHANICAL, ELECTRICAL, & PLUMBING ROOM 114 FIRST LEVEL
FEEDER SOURCE: MDP PANEL
VOLTAGE: 208/120V, 200A, 3Φ, 4W W/MLO
ENCLOSURE: SURFACE MOUNTED W/ EQUIPMENT GND BAR SQ D TYPE QO LOAD CENTER

| CKT NO | THHN WIRE SIZE | LOAD DESCRIPTION LOCATION | BREAKER AMP | BREAKER POLE | LOAD (VA) | LOAD (VA) | BREAKER POLE | BREAKER AMP | LOAD DESCRIPTION LOCATION | THHN WIRE SIZE | CKT NO |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | #12 | WOMEN'S ROOM AND MEN'S ROOM | 20 | 1 | 1000 | 200 | 1 | 20 | RECEPTACLE, GAMING ROOM | #12 | 2 |
| 3 | #12 | PORCH CHAIRS, A/C EQUIP. | 20 | 1 | 1000 | 200 | 1 | 20 | RECEPTACLE, GAMING ROOM | #12 | 4 |
| 5 | #12 | RECEPTACLES, CONFERENCE ROOM 140 | 20 | 1 | 540 | 200 | 1 | 20 | RECEPTACLE, GAMING ROOM | #12 | 6 |
| 7 | #12 | RECEPTACLES, CONFERENCE ROOM 141 | 20 | 1 | 540 | 1080 | 1 | 20 | RECEPTACLES, LOUNGE, LOBBY, OUTSIDE | #12 | 8 |
| 9 | #12 | RECEPTACLES, MUD ROOM AND HALLWAY | 20 | 1 | 540 | 1500 | 1 | 20 | DEDICATED RECEPTACLE, AT BAR IN LOUNGE | #12 | 10 |
| 11 | #12 | RECEPTACLES, EXERCISE ROOM AND OUTSIDE | 20 | 1 | 900 | 1500 | 1 | 20 | DEDICATED RECEPTACLE, AT BAR IN LOUNGE | #12 | 12 |
| 13 | #12 | DEDICATED RECEPTACLE, EXERCISE ROOM | 20 | 1 | 1500 | 1500 | 1 | 20 | RECEPTACLES, AT BAR IN LOUNGE | #12 | 14 |
| 15 | #12 | DEDICATED RECEPTACLE, EXERCISE ROOM | 20 | 1 | 1500 | 1500 | 1 | 20 | DEDICATED RECEPTACLE, AT BAR IN LOUNGE | #12 | 16 |
| 17 | #12 | DEDICATED RECEPTACLE NEAR STAIRS, OPPOSITE END OF BUILDING | 20 | 1 | 1500 | 1500 | 1 | 20 | DEDICATED RECEPTACLE, AT BAR IN LOUNGE | #12 | 18 |
| 19 | #12 | DEDICATED RECEPTACLE NEAR STAIRS, OPPOSITE END OF BUILDING | 20 | 1 | 1500 | 1500 | 1 | 20 | DEDICATED RECEPTACLE, AT BAR IN LOUNGE | #12 | 20 |
| 21 | #12 | LIGHTING, MENS ROOM, WOMENS ROOM, CENTER OF HALLWAY | 20 | 1 | 640 | 1500 | 1 | 20 | DEDICATED RECEPTACLE, AT BAR IN LOUNGE | #12 | 22 |
| 23 | #12 | LIGHTING, LOUNGE AND GAMING | 20 | 1 | 640 | 591 | 1 | 20 | LIGHTING, EXERCISE ROOM | #12 | 24 |
| 25 | #12 | LIGHTING, CONFERENCE ROOM | 20 | 1 | 990 | | 1 | 20 | SPARE | | 26 |
| 27 | #12 | LIGHTING, OPPOSITE END OF HALL AND STORAGE ROOM | 20 | 1 | 896 | | 1 | 20 | SPARE | | 28 |
| 29 | #12 | LIGHTING, MUD ROOM | 20 | 1 | 591 | | 1 | 20 | SPARE | | 30 |
| 31 | | SPARE | 20 | 1 | | | 1 | 20 | SPARE | | 32 |
| 33 | | SPARE | 20 | 1 | | | 1 | 20 | SPARE | | 34 |
| 35 | | SPARE | 20 | 1 | | | 1 | 20 | SPARE | | 36 |
| 37 | | SPARE | 20 | 1 | | | 1 | 20 | SPARE | | 38 |
| 39 | | SPARE | 20 | 1 | | | 1 | 20 | SPARE | | 40 |
| 41 | | SPARE | 20 | 1 | | | 1 | 20 | SPARE | | 42 |

SOLID NEUTRAL NEUTRAL WIRE (N) — TOTAL CONNECTED LOAD (VA) = 27,048 — GROUND BUS GROUND WIRE (G)
AΦ = 9,810 BΦ = 9,276 CΦ = 7,962

# PANEL SCHEDULE

PANEL: P15
LOCATION: MECHANICAL, ELECTRICAL, & PLUMBING ROOM 114 FIRST LEVEL
FEEDER SOURCE: MDP PANEL
VOLTAGE: 208/120V, 200A, 3Φ, 4W W/MLO
ENCLOSURE: SURFACE MOUNTED W/ EQUIPMENT GND BAR SQ D TYPE QO LOAD CENTER

| CKT NO | THHN WIRE SIZE | LOAD DESCRIPTION LOCATION | BREAKER AMP | BREAKER POLE | LOAD (VA) | LOAD (VA) | BREAKER POLE | BREAKER AMP | LOAD DESCRIPTION LOCATION | THHN WIRE SIZE | CKT NO |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | #10 | COOK TOP TWO BURNER, SUITE 117 | 30 | 1 | 2400 | 0 | 1 | 20 | SPARE | #12 | 2 |
| 3 | #10 | COOK TOP TWO BURNER, SUITE 132 | 30 | 1 | 2400 | 0 | 1 | 20 | SPARE | #12 | 4 |
| 5 | #10 | COOK TOP TWO BURNER, SUITE 133 | 30 | 1 | 2400 | 1500 | 1 | 20 | REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 133 | #12 | 6 |
| 7 | #10 | COOK TOP TWO BURNER, SUITE 134 | 30 | 1 | 2400 | 1000 | 1 | 20 | MICROWAVE OVEN, SUITE 133 | #12 | 8 |
| 9 | #10 | COOK TOP TWO BURNER, SUITE 135 | 30 | 1 | 2400 | 1000 | 1 | 20 | DISH WASHER AND GARBAGE DISPOSAL, SUITE 133 | #12 | 10 |
| 11 | #12 | REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 117 | 20 | 1 | 1500 | 1080 | 1 | 20 | RECEPTACLES AND LIGHTING, SUITE 133 | #12 | 12 |
| 13 | #12 | MICROWAVE OVEN, SUITE 117 | 20 | 1 | 1000 | 720 | 1 | 20 | BATHROOM RECEPTACLES AND LIGHTING SUITE 133 | #12 | 14 |
| 15 | #12 | DISH WASHER AND GARBAGE DISPOSAL, SUITE 117 | 20 | 1 | 1000 | 1500 | 1 | 20 | REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 134 | #12 | 16 |
| 17 | #12 | RECEPTACLES AND LIGHTING, SUITE 117 | 20 | 1 | 1080 | 1000 | 1 | 20 | MICROWAVE OVEN, SUITE 134 | #12 | 18 |
| 19 | #12 | BATHROOM RECEPTACLES AND LIGHTING SUITE 117 | 20 | 1 | 720 | 1000 | 1 | 20 | DISH WASHER AND GARBAGE DISPOSAL, SUITE 134 | #12 | 20 |
| 21 | #12 | REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 132 | 20 | 1 | 1500 | 1080 | 1 | 20 | RECEPTACLES AND LIGHTING, SUITE 134 | #12 | 22 |
| 23 | #12 | MICROWAVE OVEN, SUITE 132 | 20 | 1 | 1000 | 720 | 1 | 20 | BATHROOM RECEPTACLES AND LIGHTING SUITE 134 | #12 | 24 |
| 25 | #12 | DISH WASHER AND GARBAGE DISPOSAL, SUITE 132 | 20 | 1 | 1000 | 1500 | 1 | 20 | REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 135 | #12 | 26 |
| 27 | #12 | RECEPTACLES AND LIGHTING, SUITE 132 | 20 | 1 | 1080 | 1000 | 1 | 20 | MICROWAVE OVEN, SUITE 135 | #12 | 28 |
| 29 | #12 | BATHROOM RECEPTACLES AND LIGHTING SUITE 132 | 20 | 1 | 720 | 1000 | 1 | 20 | DISH WASHER AND GARBAGE DISPOSAL, SUITE 135 | #12 | 30 |
| 31 | #12 | SUITE 117 PTAC 208V RECEPTACLE | 20 | 2 | 1750 | 1080 | 1 | 20 | RECEPTACLES AND LIGHTING, SUITE 135 | #12 | 32 |
| 33 | | | | | 1750 | 720 | 1 | 20 | BATHROOM RECEPTACLES AND LIGHTING SUITE 135 | #12 | 34 |
| 35 | #12 | SUITE 132 PTAC 208V RECEPTACLE | 20 | 2 | 1750 | 1750 | 2 | 20 | SUITE 133 PTAC 208V RECEPTACLE | #12 | 36 |
| 37 | | | | | 1750 | 1750 | | | | | 38 |
| 39 | #12 | SUITE 134 PTAC 208V RECEPTACLE | 20 | 2 | 1750 | 1750 | 2 | 20 | SUITE 135 PTAC 208V RECEPTACLE | #12 | 40 |
| 41 | | | | | 1750 | 1750 | | | | | 42 |

SOLID NEUTRAL NEUTRAL WIRE (N) — TOTAL CONNECTED LOAD (VA) = 56,000 — GROUND BUS GROUND WIRE (G)
AΦ = 18,070 BΦ = 18,930 CΦ = 19,000

DAMMON ENGINEERING, INC.
LOUISIANA & MISSISSIPPI
Chief Engineer: Brian Mistich, PE
554 Old Spanish Trail
Slidell, LA 70458
www.dammonengineering.com
info@dammonengineering.com
PH: 985.649.5832 F: 985.641.5950

REVISIONS

| # | DESCRIPTION | DATE |
|---|---|---|

SEAL: STATE OF LOUISIANA — BRIAN A. MISTICH — License No. 30187 — PROFESSIONAL ENGINEER — 02-19-16

MAIN STAY SUITES
700 MAIN STREET
LOT #7 LA HWY 27
HACKBERRY, LA 70645

JOB No: 2265 DATE: FEBRUARY, 2016
DRAWN BY: DD/JTL CHECKED BY: BAM

The above drawings and specifications, designs and arrangements represented thereby are and shall remain the property of Dammon Engineering, and no part thereof shall be copied, disclosed to others, or used in connection with any work or project other than the specific project for which the have been prepared and developed without written consent of Dammon Engineering. Visual contact with these drawings or specifications shall constitute conclusive evidence of acceptance of these restrictions.

SHEET TITLE: ELECTRICAL PANEL SCHEDULES, FIRST FLOOR

DRAWING NUMBER: E106