PANEL SCHEDULE

PANEL: P21
LOCATION: MECHANICAL, ELECTRICAL, & PLUMBING ROOM 209 SECOND LEVEL
FEEDER SOURCE: MDP PANEL
VOLTAGE: 208/120V, 400A, 3Φ, 4W W/MLO
ENCLOSURE: SURFACE MOUNTED W/ EQUIPMENT GND BAR SQ D TYPE NQ PANELBOARD

CKT NO	THHN WIRE SIZE	LOAD DESCRIPTION LOCATION	BREAKER AMP	BREAKER POLE	LOAD (VA)	LOAD (VA)	BREAKER POLE	BREAKER AMP	LOAD DESCRIPTION LOCATION	THHN WIRE SIZE	CKT NO
1	#12	DEDICATED RECEPTACLE NEAR STAIRS, OPPOSITE END OF BUILDING	20	1	1500	720	1	20	RECEPTACLES, MAINT. ROOM AT OPPOSITE END OF BUILDING AND HALLWAY	#12	2
3	#12	DEDICATED RECEPTACLE NEAR STAIRS, OPPOSITE END OF BUILDING	20	1	1500	720	1	20	RECEPTACLES, LAUNDRY ROOM HOUSEKEEPING AND HALLWAY	#12	4
5		SPARE	20	1		180	1	20	RECEPTACLE, THIS ROOM	#12	6
7		SPARE	20	1		743	1	20	LIGHTING, THIS END OF HALL	#12	8
9		SPARE	20	1		315	1	20	LIGHTING, STAIRS AND EQUIPMENT ROOM, THIS END OF BUILDING	#12	10
11		SPARE	20	1		434	1	20	LIGHTING, HOUSEKEEPING, LAUNDRY AND ELEVATOR LOBBY	#12	12
13		SPARE	20	1		512	1	20	LIGHTS, CENTER OF HALL	#12	14
15		SPARE	20	1		644	1	20	LIGHTING, OPPOSITE END OF HALLWAY	#12	16
17		SPARE	20	1		628	1	20	LIGHTING, STAIRS AND MAINTENANCE ROOM OPPOSITE END OF BUILDING	#12	18
19					19820		1	20	SPARE		20
21	#4/0	PANEL P22	175	3	20680		1	20	SPARE		22
23					19000		1	20	SPARE		24
25					18070		1	20	SPARE		26
27	#4/0	PANEL P23	175	3	18930		1	20	SPARE		28
29					19000		1	20	SPARE		30
31					18070	3333					32
33	#4/0	PANEL P24	175	3	18930	3333	3	60	2 1/2 TON HVAC UNIT, 2ND LEVEL 10 KW HEAT	#6	34
35					19000	3333					36
37					18070	18070					38
39	#4/0	PANEL P25	175	3	18930	18930	3	175	PANEL P26	#4/0	40
41					19000	19000					42

SOLID NEUTRAL NEUTRAL WIRE (N) — TOTAL CONNECTED LOAD (VA) = 301,395 — AΦ = 98,908 BΦ = 102,912 CΦ = 99,575 — GROUND BUS GROUND WIRE (G)

PANEL SCHEDULE

PANEL: P23
LOCATION: MECHANICAL, ELECTRICAL, & PLUMBING ROOM 209 SECOND LEVEL
FEEDER SOURCE: MDP PANEL
VOLTAGE: 208/120V, 200A, 3Φ, 4W W/MLO
ENCLOSURE: SURFACE MOUNTED W/ EQUIPMENT GND BAR SQ D TYPE QO LOAD CENTER

CKT NO	THHN WIRE SIZE	LOAD DESCRIPTION LOCATION	BREAKER AMP	BREAKER POLE	LOAD (VA)	LOAD (VA)	BREAKER POLE	BREAKER AMP	LOAD DESCRIPTION LOCATION	THHN WIRE SIZE	CKT NO
1	#10	COOK TOP TWO BURNER, SUITE 206	30	1	2400	0	1	20	SPARE	#12	2
3	#10	COOK TOP TWO BURNER, SUITE 207	30	1	2400	0	1	20	SPARE	#12	4
5	#10	COOK TOP TWO BURNER, SUITE 210	30	1	2400	1500	1	20	REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 210	#12	6
7	#10	COOK TOP TWO BURNER, SUITE 211	30	1	2400	1000	1	20	MICROWAVE OVEN, SUITE 210	#12	8
9	#10	COOK TOP TWO BURNER, SUITE 212	30	1	2400	1000	1	20	DISH WASHER AND GARBAGE DISPOSAL, SUITE 210	#12	10
11	#12	REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 206	20	1	1500	1080	1	20	RECEPTACLES AND LIGHTING, SUITE 210	#12	12
13	#12	MICROWAVE OVEN, SUITE 206	20	1	1000	720	1	20	BATHROOM RECEPTACLES AND LIGHTING SUITE 210	#12	14
15	#12	DISH WASHER AND GARBAGE DISPOSAL, SUITE 206	20	1	1000	1500	1	20	REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 211	#12	16
17	#12	RECEPTACLES AND LIGHTING, SUITE 206	20	1	1080	1000	1	20	MICROWAVE OVEN, SUITE 211	#12	18
19	#12	BATHROOM RECEPTACLES AND LIGHTING SUITE 206	20	1	720	1000	1	20	DISH WASHER AND GARBAGE DISPOSAL, SUITE 211	#12	20
21	#12	REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 207	20	1	1500	1080	1	20	RECEPTACLES AND LIGHTING, SUITE 211	#12	22
23	#12	MICROWAVE OVEN, SUITE 207	20	1	1000	720	1	20	BATHROOM RECEPTACLES AND LIGHTING SUITE 211	#12	24
25	#12	DISH WASHER AND GARBAGE DISPOSAL, SUITE 207	20	1	1000	1500	1	20	REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 212	#12	26
27	#12	RECEPTACLES AND LIGHTING, SUITE 207	20	1	1080	1000	1	20	MICROWAVE OVEN, SUITE 212	#12	28
29	#12	BATHROOM RECEPTACLES AND LIGHTING SUITE 207	20	1	720	1000	1	20	DISH WASHER AND GARBAGE DISPOSAL, SUITE 212	#12	30
31	#12	SUITE 206 PTAC 208V RECEPTACLE	20	2	1750	1080	1	20	RECEPTACLES AND LIGHTING, SUITE 212	#12	32
33					1750	720	1	20	BATHROOM RECEPTACLES AND LIGHTING SUITE 212	#12	34
35	#12	SUITE 207 PTAC 208V RECEPTACLE	20	2	1750	1750	2	20	SUITE 211 PTAC 208V RECEPTACLE	#12	36
37					1750	1750					38
39	#12	SUITE 210 PTAC 208V RECEPTACLE	20	2	1750	1750	2	20	SUITE 212 PTAC 208V RECEPTACLE	#12	40
41					1750	1750					42

SOLID NEUTRAL NEUTRAL WIRE (N) — TOTAL CONNECTED LOAD (VA) = 56,000 — AΦ = 18,070 BΦ = 18,930 CΦ = 19,000 — GROUND BUS GROUND WIRE (G)

PANEL SCHEDULE

PANEL: P25
LOCATION: MECHANICAL, ELECTRICAL, & PLUMBING ROOM 209 SECOND LEVEL
FEEDER SOURCE: MDP PANEL
VOLTAGE: 208/120V, 200A, 3Φ, 4W W/MLO
ENCLOSURE: SURFACE MOUNTED W/ EQUIPMENT GND BAR SQ D TYPE QO LOAD CENTER

CKT NO	THHN WIRE SIZE	LOAD DESCRIPTION LOCATION	BREAKER AMP	BREAKER POLE	LOAD (VA)	LOAD (VA)	BREAKER POLE	BREAKER AMP	LOAD DESCRIPTION LOCATION	THHN WIRE SIZE	CKT NO
1	#10	COOK TOP TWO BURNER, SUITE 220	30	1	2400	0	1	20	SPARE	#12	2
3	#10	COOK TOP TWO BURNER, SUITE 221	30	1	2400	0	1	20	SPARE	#12	4
5	#10	COOK TOP TWO BURNER, SUITE 222	30	1	2400	1500	1	20	REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 222	#12	6
7	#10	COOK TOP TWO BURNER, SUITE 223	30	1	2400	1000	1	20	MICROWAVE OVEN, SUITE 222	#12	8
9	#10	COOK TOP TWO BURNER, SUITE 227	30	1	2400	1000	1	20	DISH WASHER AND GARBAGE DISPOSAL, SUITE 222	#12	10
11	#12	REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 220	20	1	1500	1080	1	20	RECEPTACLES AND LIGHTING, SUITE 222	#12	12
13	#12	MICROWAVE OVEN, SUITE 220	20	1	1000	720	1	20	BATHROOM RECEPTACLES AND LIGHTING SUITE 222	#12	14
15	#12	DISH WASHER AND GARBAGE DISPOSAL, SUITE 220	20	1	1000	1500	1	20	REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 223	#12	16
17	#12	RECEPTACLES AND LIGHTING, SUITE 220	20	1	1080	1000	1	20	MICROWAVE OVEN, SUITE 223	#12	18
19	#12	BATHROOM RECEPTACLES AND LIGHTING SUITE 220	20	1	720	1000	1	20	DISH WASHER AND GARBAGE DISPOSAL, SUITE 223	#12	20
21	#12	REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 221	20	1	1500	1080	1	20	RECEPTACLES AND LIGHTING, SUITE 223	#12	22
23	#12	MICROWAVE OVEN, SUITE 221	20	1	1000	720	1	20	BATHROOM RECEPTACLES AND LIGHTING SUITE 223	#12	24
25	#12	DISH WASHER AND GARBAGE DISPOSAL, SUITE 221	20	1	1000	1500	1	20	REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 227	#12	26
27	#12	RECEPTACLES AND LIGHTING, SUITE 221	20	1	1080	1000	1	20	MICROWAVE OVEN, SUITE 227	#12	28
29	#12	BATHROOM RECEPTACLES AND LIGHTING SUITE 221	20	1	720	1000	1	20	DISH WASHER AND GARBAGE DISPOSAL, SUITE 227	#12	30
31	#12	SUITE 220 PTAC 208V RECEPTACLE	20	2	1750	1080	1	20	RECEPTACLES AND LIGHTING, SUITE 227	#12	32
33					1750	720	1	20	BATHROOM RECEPTACLES AND LIGHTING SUITE 227	#12	34
35	#12	SUITE 221 PTAC 208V RECEPTACLE	20	2	1750	1750	2	20	SUITE 223 PTAC 208V RECEPTACLE	#12	36
37					1750	1750					38
39	#12	SUITE 222 PTAC 208V RECEPTACLE	20	2	1750	1750	2	20	SUITE 227 PTAC 208V RECEPTACLE	#12	40
41					1750	1750					42

SOLID NEUTRAL NEUTRAL WIRE (N) — TOTAL CONNECTED LOAD (VA) = 56,000 — AΦ = 18,070 BΦ = 18,930 CΦ = 19,000 — GROUND BUS GROUND WIRE (G)

PANEL SCHEDULE

PANEL: P22
LOCATION: MECHANICAL, ELECTRICAL, & PLUMBING ROOM 209 SECOND LEVEL
FEEDER SOURCE: MDP PANEL
VOLTAGE: 208/120V, 200A, 3Φ, 4W W/MLO
ENCLOSURE: SURFACE MOUNTED W/ EQUIPMENT GND BAR SQ D TYPE QO LOAD CENTER

CKT NO	THHN WIRE SIZE	LOAD DESCRIPTION LOCATION	BREAKER AMP	BREAKER POLE	LOAD (VA)	LOAD (VA)	BREAKER POLE	BREAKER AMP	LOAD DESCRIPTION LOCATION	THHN WIRE SIZE	CKT NO
1	#10	COOK TOP TWO BURNER, SUITE 201	30	1	2400	1500	1	20	REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 203	#12	2
3	#10	COOK TOP TWO BURNER, SUITE 202	30	1	2400	1000	1	20	MICROWAVE OVEN, SUITE 203	#12	4
5	#10	COOK TOP TWO BURNER, SUITE 203	30	1	2400	1000	1	20	DISH WASHER AND GARBAGE DISPOSAL, SUITE 203	#12	6
7	#10	COOK TOP TWO BURNER, SUITE 204	30	1	2400	1080	1	20	RECEPTACLES AND LIGHTING, SUITE 203	#12	8
9	#10	COOK TOP TWO BURNER, SUITE 205	30	1	2400	720	1	20	BATHROOM RECEPTACLES AND LIGHTING SUITE 203	#12	10
11	#12	REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 201	20	1	1500	1500	1	20	REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 204	#12	12
13	#12	MICROWAVE OVEN, SUITE 201	20	1	1000	1000	1	20	MICROWAVE OVEN, SUITE 204	#12	14
15	#12	DISH WASHER AND GARBAGE DISPOSAL, SUITE 201	20	1	1000	1000	1	20	DISH WASHER AND GARBAGE DISPOSAL, SUITE 204	#12	16
17	#12	RECEPTACLES AND LIGHTING, SUITE 201	20	1	1080	1080	1	20	RECEPTACLES AND LIGHTING, SUITE 204	#12	18
19	#12	BATHROOM RECEPTACLES AND LIGHTING SUITE 201	20	1	720	720	1	20	BATHROOM RECEPTACLES AND LIGHTING SUITE 204	#12	20
21	#12	REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 202	20	1	1500	1500	1	20	REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 205	#12	22
23	#12	MICROWAVE OVEN, SUITE 202	20	1	1000	1000	1	20	MICROWAVE OVEN, SUITE 205	#12	24
25	#12	DISH WASHER AND GARBAGE DISPOSAL, SUITE 202	20	1	1000	1000	1	20	DISH WASHER AND GARBAGE DISPOSAL, SUITE 205	#12	26
27	#12	RECEPTACLES AND LIGHTING, SUITE 202	20	1	1080	1080	1	20	RECEPTACLES AND LIGHTING, SUITE 205	#12	28
29	#12	BATHROOM RECEPTACLES AND LIGHTING SUITE 202	20	1	720	720	1	20	BATHROOM RECEPTACLES AND LIGHTING SUITE 205	#12	30
31	#12	SUITE 201 PTAC 208V RECEPTACLE	20	2	1750	1750	2	20	SUITE 203 PTAC, 208V RECEPTACLE IN BEDROOM	#12	32
33					1750	1750					34
35	#12	SUITE 202 PTAC 208V RECEPTACLE	20	2	1750	1750	2	20	SUITE 204 PTAC 208V RECEPTACLE	#12	36
37					1750	1750					38
39	#12	SUITE 203 PTAC 208V RECEPTACLE IN LIVING ROOM	20	2	1750	1750	2	20	SUITE 205 PTAC 208V RECEPTACLE	#12	40
41					1750	1750					42

SOLID NEUTRAL NEUTRAL WIRE (N) — TOTAL CONNECTED LOAD (VA) = 59,500 — AΦ = 19,820 BΦ = 20,680 CΦ = 19,000 — GROUND BUS GROUND WIRE (G)

PANEL SCHEDULE

PANEL: P24
LOCATION: MECHANICAL, ELECTRICAL, & PLUMBING ROOM 209 SECOND LEVEL
FEEDER SOURCE: MDP PANEL
VOLTAGE: 208/120V, 200A, 3Φ, 4W W/MLO
ENCLOSURE: SURFACE MOUNTED W/ EQUIPMENT GND BAR SQ D TYPE QO LOAD CENTER

CKT NO	THHN WIRE SIZE	LOAD DESCRIPTION LOCATION	BREAKER AMP	BREAKER POLE	LOAD (VA)	LOAD (VA)	BREAKER POLE	BREAKER AMP	LOAD DESCRIPTION LOCATION	THHN WIRE SIZE	CKT NO
1	#10	COOK TOP TWO BURNER, SUITE 213	30	1	2400	0	1	20	SPARE	#12	2
3	#10	COOK TOP TWO BURNER, SUITE 216	30	1	2400	0	1	20	SPARE	#12	4
5	#10	COOK TOP TWO BURNER, SUITE 217	30	1	2400	1500	1	20	REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 217	#12	6
7	#10	COOK TOP TWO BURNER, SUITE 218	30	1	2400	1000	1	20	MICROWAVE OVEN, SUITE 217	#12	8
9	#10	COOK TOP TWO BURNER, SUITE 219	30	1	2400	1000	1	20	DISH WASHER AND GARBAGE DISPOSAL, SUITE 217	#12	10
11	#12	REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 213	20	1	1500	1080	1	20	RECEPTACLES AND LIGHTING, SUITE 217	#12	12
13	#12	MICROWAVE OVEN, SUITE 213	20	1	1000	720	1	20	BATHROOM RECEPTACLES AND LIGHTING SUITE 217	#12	14
15	#12	DISH WASHER AND GARBAGE DISPOSAL, SUITE 213	20	1	1000	1500	1	20	REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 218	#12	16
17	#12	RECEPTACLES AND LIGHTING, SUITE 213	20	1	1080	1000	1	20	MICROWAVE OVEN, SUITE 218	#12	18
19	#12	BATHROOM RECEPTACLES AND LIGHTING SUITE 213	20	1	720	1000	1	20	DISH WASHER AND GARBAGE DISPOSAL, SUITE 218	#12	20
21	#12	REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 216	20	1	1500	1080	1	20	RECEPTACLES AND LIGHTING, SUITE 218	#12	22
23	#12	MICROWAVE OVEN, SUITE 216	20	1	1000	720	1	20	BATHROOM RECEPTACLES AND LIGHTING SUITE 218	#12	24
25	#12	DISH WASHER AND GARBAGE DISPOSAL, SUITE 216	20	1	1000	1500	1	20	REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 219	#12	26
27	#12	RECEPTACLES AND LIGHTING, SUITE 216	20	1	1080	1000	1	20	MICROWAVE OVEN, SUITE 219	#12	28
29	#12	BATHROOM RECEPTACLES AND LIGHTING SUITE 216	20	1	720	1000	1	20	DISH WASHER AND GARBAGE DISPOSAL, SUITE 219	#12	30
31	#12	SUITE 213 PTAC 208V RECEPTACLE	20	2	1750	1080	1	20	RECEPTACLES AND LIGHTING, SUITE 219	#12	32
33					1750	720	1	20	BATHROOM RECEPTACLES AND LIGHTING SUITE 219	#12	34
35	#12	SUITE 216 PTAC 208V RECEPTACLE	20	2	1750	1750	2	20	SUITE 218 PTAC 208V RECEPTACLE	#12	36
37					1750	1750					38
39	#12	SUITE 217 PTAC 208V RECEPTACLE	20	2	1750	1750	2	20	SUITE 219 PTAC 208V RECEPTACLE	#12	40
41					1750	1750					42

SOLID NEUTRAL NEUTRAL WIRE (N) — TOTAL CONNECTED LOAD (VA) = 56,000 — AΦ = 18,070 BΦ = 18,930 CΦ = 19,000 — GROUND BUS GROUND WIRE (G)

PANEL SCHEDULE

PANEL: P26
LOCATION: MECHANICAL, ELECTRICAL, & PLUMBING ROOM 209 SECOND LEVEL
FEEDER SOURCE: MDP PANEL
VOLTAGE: 208/120V, 200A, 3Φ, 4W W/MLO
ENCLOSURE: SURFACE MOUNTED W/ EQUIPMENT GND BAR SQ D TYPE QO LOAD CENTER

CKT NO	THHN WIRE SIZE	LOAD DESCRIPTION LOCATION	BREAKER AMP	BREAKER POLE	LOAD (VA)	LOAD (VA)	BREAKER POLE	BREAKER AMP	LOAD DESCRIPTION LOCATION	THHN WIRE SIZE	CKT NO
1	#10	COOK TOP TWO BURNER, SUITE 228	30	1	2400	0	1	20	SPARE	#12	2
3	#10	COOK TOP TWO BURNER, SUITE 229	30	1	2400	0	1	20	SPARE	#12	4
5	#10	COOK TOP TWO BURNER, SUITE 230	30	1	2400	1500	1	20	REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 230	#12	6
7	#10	COOK TOP TWO BURNER, SUITE 231	30	1	2400	1000	1	20	MICROWAVE OVEN, SUITE 230	#12	8
9	#10	COOK TOP TWO BURNER, SUITE 232	30	1	2400	1000	1	20	DISH WASHER AND GARBAGE DISPOSAL, SUITE 230	#12	10
11	#12	REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 228	20	1	1500	1080	1	20	RECEPTACLES AND LIGHTING, SUITE 230	#12	12
13	#12	MICROWAVE OVEN, SUITE 228	20	1	1000	720	1	20	BATHROOM RECEPTACLES AND LIGHTING SUITE 230	#12	14
15	#12	DISH WASHER AND GARBAGE DISPOSAL, SUITE 228	20	1	1000	1500	1	20	REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 231	#12	16
17	#12	RECEPTACLES AND LIGHTING, SUITE 228	20	1	1080	1000	1	20	MICROWAVE OVEN, SUITE 231	#12	18
19	#12	BATHROOM RECEPTACLES AND LIGHTING SUITE 228	20	1	720	1000	1	20	DISH WASHER AND GARBAGE DISPOSAL, SUITE 231	#12	20
21	#12	REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 229	20	1	1500	1080	1	20	RECEPTACLES AND LIGHTING, SUITE 231	#12	22
23	#12	MICROWAVE OVEN, SUITE 229	20	1	1000	720	1	20	BATHROOM RECEPTACLES AND LIGHTING SUITE 231	#12	24
25	#12	DISH WASHER AND GARBAGE DISPOSAL, SUITE 229	20	1	1000	1500	1	20	REFRIGERATOR AND KITCHEN COUNTER RECEPTACLES, SUITE 232	#12	26
27	#12	RECEPTACLES AND LIGHTING, SUITE 229	20	1	1080	1000	1	20	MICROWAVE OVEN, SUITE 232	#12	28
29	#12	BATHROOM RECEPTACLES AND LIGHTING SUITE 229	20	1	720	1000	1	20	DISH WASHER AND GARBAGE DISPOSAL, SUITE 232	#12	30
31	#12	SUITE 228 PTAC 208V RECEPTACLE	20	2	1750	1080	1	20	RECEPTACLES AND LIGHTING, SUITE 232	#12	32
33					1750	720	1	20	BATHROOM RECEPTACLES AND LIGHTING SUITE 232	#12	34
35	#12	SUITE 229 PTAC 208V RECEPTACLE	20	2	1750	1750	2	20	SUITE 231 PTAC 208V RECEPTACLE	#12	36
37					1750	1750					38
39	#12	SUITE 230 PTAC 208V RECEPTACLE	20	2	1750	1750	2	20	SUITE 232 PTAC 208V RECEPTACLE	#12	40
41					1750	1750					42

SOLID NEUTRAL NEUTRAL WIRE (N) — TOTAL CONNECTED LOAD (VA) = 56,000 — AΦ = 18,070 BΦ = 18,930 CΦ = 19,000 — GROUND BUS GROUND WIRE (G)

DAMMON ENGINEERING, INC.
LOUISIANA & MISSISSIPPI
Chief Engineer: Brian Mistich, PE
554 Old Spanish Trail
Slidell, LA 70458
www.dammonengineering.com
info@dammonengineering.com
PH: 985.649.5832 F: 985.641.5950

REVISIONS

#	DESCRIPTION	DATE

SEAL: STATE OF LOUISIANA — BRIAN A. MISTICH License No. 30187 — PROFESSIONAL ENGINEER — 02-19-16

MAIN STAY SUITES
700 MAIN STREET
LOT #7 LA HWY 27
HACKBERRY, LA 70645

JOB No: 2265 | DATE: FEBRUARY, 2016
DRAWN BY: DD/JTL | CHECKED BY: BAM

The above drawings and specifications, designs and arrangements represented thereby are and shall remain the property of Dammon Engineering, and no part thereof shall be copied, disclosed to others, or used in connection with any work or project other than the specific project for which the have been prepared and developed without written consent of Dammon Engineering. Visual contact with these drawings or specifications shall constitute conclusive evidence of acceptance of these restrictions.

SHEET TITLE: ELECTRICAL PANEL SCHEDULES, SECOND FLOOR

DRAWING NUMBER: E107